

CURRENT CITY PROJECT

(As of March 3, 2009)

Cedarwood Area Reconstruction

Contracts have been awarded for the reconstruction of the waterlines and sanitary sewer rehabilitation in the Cedarwood Subdivision Area and for sanitary sewer rehabilitation in several other areas of the City.

The waterline reconstruction project is estimated at 190 calendar days and we anticipate the notice to proceed to be March 9th with a completion date in September.

The sanitary sewer rehab project has a construction time of 180 calendar days. Notice to proceed will be issued on March 23rd with a completion date in September. The sanitary sewer project includes Cedarwood Subdivision Sections 2 and 4, plus four other areas of the City. These areas are the Bracher area, the Teresa/Ben Hur area, Bonnie Oaks, and the Hilldale/Bade area.

The final design contract for the Cedarwood Paving and Drainage Reconstruction project was awarded this month, and design work will begin immediately and continue through the end of September. Construction of the paving and drainage improvements will begin immediately after the waterline and sanitary projects in that area are completed. The design concept for the Cedarwood project will utilize an open ditch drainage system with selected areas of low-flow storm sewers (to minimize ditch depth), along with a 20-foot asphalt pavement.